

# WEST DES MOINES WATER WORK BOARD OF TRUSTEES MEETING COMMUNICATION

DATE: November 19, 2018

ITEM:

5. Consent Agenda

f. Motion

Concurring with Staff Approval of Change Order #1 for the
 2018 Water Main Replacement Project – Valves at Various Locations

## FINANCIAL IMPACT:

Net increase of \$14,229.56

# SUMMARY:

This change order incorporates additional contractor costs to shift the location of the planned valve on the west side of Jordan Creek. This change was made due to the uncertainties with pipe location and difficulty of accessing the pipe at the originally planned location. It also incorporates additional costs for rock backfill in the two street patch areas. Rock backfill is required by the City of West Des Moines for excavations within the street. Finally, the change order also includes bid item quantity adjustments to reconcile the planned quantity with the quantity actually used in the field.

#### **BACKGROUND:**

West Des Moines Water Works has systematically replaced water mains which have required numerous and expensive repairs or which data have shown produced discolored water due to tuberculation. This project is targeting areas with known large diameter inoperable valves.

### RECOMMENDED ACTION BY THE BOARD OF TRUSTEES:

That The Board of Trustees concur with Staff approval of Change Orders #1 as set out in the attached documents.

Prepared by:

Approved for Content by:



West Des Moines Water Works 4200 Mills Civic Parkway, Suite 1D West Des Moines, Iowa 50265 515.222.3510

# **CHANGE ORDER**

Distribution: Owner Engineer Contractor Field Other

X	
X	
X	
X	

Project:	2018 Water Main Replacement - Valves at	Change Order No.	- A
Various Locations  To Cory Juergens Construction, LLC  Contractor: 219 W 2 St S  Estherville, IA 51334	· · · · · · · · · · · · · · · · · · ·	Date	November 1, 2018
	WDMWW Project No.	00800-170-18006	
	Estherville, IA 51334	Original Contract Date	May 21, 2018

This contract is changed as follows:

Item	Description	Value Adjustment
1	Fittings by Weight – Quantity Adjustment. (Add 28.44 LBS at \$55.00/LB)	\$1,564.20
2	Valve, Gate, DIMJ, 8" DIA. – Quantity Adjustment. (Deduct 1 EA at \$3,000.00/EA)	
6	Removal Of Walk, Path, Or Driveway – Quantity Adjustment. (Deduct 30 SY at \$20.00/SY)	-\$600.00
7	Shared Use Path, PCC, Class C-4 Reinf, 6" Thick – Quantity Adjustment. (Deduct 33.3 SY at \$62.00/SY)	-\$2,064.60
8	Sidewalk, PCC, Class C-4, 4" Thickness – Quantity Adjustment. (Add 3.3 SY at \$62.00/SY)	\$204.60
9	Full Depth Patch, Reinforced PCC Class M-4 – Quantity Adjustment. (Add 67 SY at \$140.00/SY)	
10	Temporary Traffic Control – Quantity Adjustment. (Add 0.28 LS at \$5,000.00/LS)	\$1,400.00
CO-1	Substitute rock for in-situ soil backfill (Material) – Due to wet conditions, excavations in EP True Parkway were backfilled with granular material. (341.63 TON at \$14.00/TON)	\$4,782.86
00-2	Substitute rock for in-situ soil backfill (Labor) (1 LS at \$2,562.50/LS)	\$2,562.50

	The origin	al (Contract Sum) was	\$190,525.80
	No Change		
	\$190,525.80		
	\$14,229.56		
The (Contract Sum) will be (increased) by this Change Order in the amount of  The new (Contract Sum) including this Change order will be			\$204,755.36
	The new (Contract Sum) including the	e will be (increased) by	No change
	of Substantial Completion as of the date of this Cha	ange Order therefore is	No change
The date of	ED BY THE CONTRACTOR, OWNER'S REPRES	SENTATIVE, if applicable	, AND OWNER
Contractor: Cory Juergens Construction By: Cory Juergens Title: Owner Date: 11 9 8	Owner's Representative:  West Des Moines Water Works  By: Kevin Trevillyan  Title: Engineering Technician  Ver L. Turk	Owner: West Des Moines W By: William Mabus Title: Engineering P Date: // 9/8	ater Works ce, PE
Owner: West Des Moines Water	Engineering Project Manager X		)ate
☑ up to \$15,000.00	General Manager x		)ate
☐ up to \$25,000.00	Board of Trustees Committee X		Date
		-	Date

Board of Trustees

☐ greater than \$25,000.00

Date \_\_\_\_